

1st Catisfield Scout Group : New HQ Building

		MATERIALS	PROVIDED BY	LABOUR	VOLUNTEERS
Foundations and site works	quantity required				
Concrete	175 m³	Can anyone supply us with readymix concrete of different grades for foundations and various hard surfaces on the site?		General labourers are required for heavy digging and concrete placing	
Steel frame	16 tonnes	We require structural steel sections for the structural frame of the building comprising standard 'I' sections for columns and roof beams; cold rolled sheeting rails and purlins for the roof and gable wall cladding including cleats and accessories		Steel erectors required. Does anybody possess this skill or know someone or A firm who would be able to help?	
Profiled steel composite sheet roofing and cladding	876 m²	We require profiled steel sheet cladding materials, flashings and the like for the built-up roof and gable wall coverings including insulation and inner sheeting. Alternatively we will install a composite panel on the vertical surfaces and a standing seam type aluminium roof.		We require a friendly roofing and cladding company to undertake this major element of the new building. Can anyone help?	
Rooflights	65 m²	These are translucent double skin panels inserted into the roof panels		These will be installed by the friendly roofer	
Brick and block walls					
Facing bricks	20000 bricks	We require 20,000 facing bricks, colour yellow or buff (exact colour needs to be agreed with the planning authority)		Bricklayers and labourers are required to build the external cavity walls and the internal block walls	
Light weight insulating concrete blocks 150mm thick	3000 blocks	We require 3,000 lightweight insulating blocks, 140mm thick and 4,000 fair face concrete blocks 100mm thick for the inner skin of the external walls and the internal walls			
Lightweight concrete blocks 100mm thick	4000 blocks				

1st Catisfield Scout Group : New HQ Building

		MATERIALS	PROVIDED BY	LABOUR	VOLUNTEERS
Joinery work					
Hardwood windows				Carpenters and painters are required to install windows and door sets, erect prefabricated toilet cubicles, assemble and install kitchen units, build shelving and storage units, fix ironmongery and fittings	
1200 x 300	3 nr	We require windows and external doors in the numbers shown. These could be aluminium or plastic instead of hardwood if these alternatives were available.			
1800 x 1200	2 nr				
3600 x 2100 including double doors	1 nr				
Painted external doors in hardwood frame					
single	1 nr				
double	2 nr				
Hardwood glazed external door in hardwood frame					
single	1 nr				
double	1 nr				
Toilet cubicles		Can anyone supply three ranges of proprietary toilet cubicles?			
range of two (infants)	1 nr				
range of three (adult)	2 nr				
Internal doors		We need internal doors and frames. Some of the doors will be half hour fire resisting. All the doors need to be solid core. They can be veneered or painted - we don't mind; whatever is available			
single door and frame	7 nr				
double door and frame	8 nr				
servicing hatch and shutter	2 nr	We have two serving hatches in the kitchen which can be painted softwood frame with a fire resisting roller shutter.			
Softwood skirting	200 m	Softwood skirting 100mm high for painting			
Kitchen units		We require a range of robust kitchen units (any brand), plus worktops. The kitchen can be configured to suit the units available.			
double base units	4 nr				
sink base unit	1 nr				
double wall units	4 nr				
worktop	9 m				
Disabled toilet fitting pack	1 nr	This is the standard pack of grab rails and fittings for installing in the designated disabled WC			
Shelving and racking in stores	2 nr	Softwood framing and boarding (which can be chipboard, blockboard, mdf or even plywood - whatever is available, plus nails, screws, ironmongery (for cupboard doors)			
Storage units in main hall	1 nr				

1st Catisfield Scout Group : New HQ Building

		MATERIALS	PROVIDED BY	LABOUR	VOLUNTEERS
Finishes					
Plaster	600 m ²	Can anyone supply us with plaster in sufficient quantities for plastering the walls of the building (we may change to painted fair face walls in the main halls)		We need plasterers, tilers, floor layers and painters to plaster the walls, install plasterboard and plaster ceilings in the entrance, toilets and kitchen, install wall tiling in the toilets and kitchen, lay vinyl flooring and for general painting works	
Wall tiling	150 m ²	Plain white or lightly patterned ceramic wall tiling, 150 x 150mm tiles or similar, tile adhesive and grout for tiling the walls in the toilets and the kitchen			
Vinyl flooring	232 m ²	Non-slip vinyl sheet flooring plus flooring adhesive for the main hall floor, toilets, kitchen and entrance lobby			
Sprung Maple Floor	111 m ²	If there is anyone who installs sprung floors or knows someone who does and would be interested in helping our Group we would love to hear from you. The second hall will be used for the dancing school and we would really like to replicate the sprung floor that we have in the existing small hut			
Plasterboard ceiling on M/F system	103 m ²	We need someone to supply the plasterboard sheeting , skim coat, etc plus the lightweight metal grid components to construct the ceilings in the entrance, hall, toilets and kitchen			
Emulsion paint	703 m ²	Large cans of trade emulsion paint - white or magnolia			
Epoxy floor paint	100 m ²	Cans of floor paint for the stores			
Paint on steel	80 m ²	Wood primer, undercoat and white gloss paint for finishing exposed steel roof beams, skirtings, door frames and the like			
Gloss paint on skirtings	200 m				

1st Catisfield Scout Group : New HQ Building

		MATERIALS	PROVIDED BY	LABOUR	VOLUNTEERS
Plumbing					
WC suite - adult	6 nr	We need sanitary fittings as listed plus waste and soil stack pipework and fittings and copper tube and fittings for the hot and cold water pipework.		Plumbers are wanted for installing the sanitary fittings, the soil and waste pipework and the hot and cold water supply pipework	
WC suite - infant	2 nr				
Wash basin and spray mixer tap	8 nr				
Range of two urinals	1 nr				
Stainless steel double bowl, double drainer sink	1 nr				
Cleaners sink	1 nr				
UPVC soil stacks and waste pipes	Item				
Hot and cold water copper pipework and fittings	Item				
Heating					
Water heaters	3 nr	We require overhead gas fired space heaters for both halls, three water heaters for the kitchen and toilets plus gas pipework and fittings		We need heating engineers to install the gas fired space heaters and the electric water heaters	
Direct warm air gas fired heaters; high level in two activity halls	Item				
Gas pipework from intake to heaters	Item				
Electrical Installations					
Electric convector heaters in toilets, kitchen and lobby	Item	Electrical switchgear and distribution boards, cable, conduit and fittings are required plus socket outlets, switches and various controllers, electric fittings such as convector heaters, vent fans, alarm sounders, call points and control panels.		Are there any electricians willing to volunteer their time and expertise to install the lighting and power systems, electric heaters, toilet extract, fire alarm and security alarms	
Kitchen extract system	1 nr				
Toilet extract ventilation	2 nr				
Electrical installation complete	Item				
Fire alarm system	Item				
Disabled toilet alarm	Item				
Security alarm system	Item				

1st Catisfield Scout Group : New HQ Building

		MATERIALS	PROVIDED BY	LABOUR	VOLUNTEERS
Site Works					
Porous paving to car parking area	300 m ²	Loads of granular material for filling underneath the paved areas, tarmacadam material for the entrance area and car parking, precast concrete kerbs and edgings. Timber close boarded fencing to repair areas of the existing dilapidated boundary fence. Metal security fencing and gates at the front of the site. Special rubber granular material for the play area surfacing. Grass turves		Plenty scope for willing volunteers to help with lots of general unskilled tasks to finish the external areas	
Tarmacadam surfacing to entrance	100 m ²				
Tarmacadam surfacing to footpaths and apron in front of hut	150 m ²				
Play area surfacing	90 m ²				
Grass turves	600 m ²				
Boundary fencing	205 m				
Security fence at entrance	40 m				
Double gates	1 nr				
Drainage					
Drainage pipes and fittings	Item	Clayware or plastic drain pipes and fittings; plastic inspection chambers and steel covers		Drainlayers step forward please.	
Manholes/inspection chambers	Item				
Utilities					
Incoming utility connections	Item	<i>specialist work</i>		<i>specialist work</i>	